# MOON Landscaping, Inc.

## Maintenance Divison

## Landscape Enhancement Proposal

| | |
|---|---|
| **Client Name** | BC Communities |
| **Client Contact** | Lisa Taylor |
| **Job Name** | Steeple Glenn Condominium |
| **Proposal Date** | May 1, 2020 |
| **Site Address** | 71 Grand National Lane Newark, DE 19702 |

| Description | Price |
|---|---|
| **Turf and Drainage Repair along Walking Trail** | $7,990.00 |
| We propose to provde the necessary labor, equipment and materials to perform the following: | |
| - Strip and remove exiting turf to be remediated | |
| - Furnish and install French Drain (35LF) along walking trail | |
| - Furnish and install solid ADS pipe under asphalt path to drain to daylight on the swale side of walking trail | |
| - Furnish and install necessary topsoil | |
| - Fine grade and sod all disturbed turf areas | |
| - Furnish and install 1.5 Tons RipRap stone at drainage inlet laid over weedbarrier membrane | |
| - All debris/spoils will be removed from the project site | |
| - Labor | |
| - Equipment | |
| - Cleanup | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| **Total Cost** | **$7,990.00** |

*All pricing is subject to sales tax and is payable by customer. No retainage is to be held. Payments are expected by due date posted on invoices. Should it become necessary to place the account with a collection agency or attorney, the owner agrees to pay all collection costs and attorney fees in addition to all other sums due. Payments not made within five days of due date shall be subject to a late charge of 1 1/2% of balance per month, which is an annual charge of 18%. Note: Installations include initial watering only. Should our services be required to supplement watering, a T & M rate will be provided.*

**Ross Grossman**
MOON Representative Print Name

MOON Representative Signature

~~Lisa Taylor~~ Paul Hannan
Client Print Name

Paul Hannan
Client Signature

STEEPLE GLENN HOA
COUNCIL PRESIDENT